

OFFICE OF THE PROJECT DIRECTOR
MPPWD (PIU) NIRMAN BHAWAN, BHOPAL
SCHEDULE OF RATES FOR BUILDING WORKS (w.e.f. 01/08/2014)

AMMENDMENT NO. 40

The Rates of Following items of Building SOR w.e.f. 01/08/2014 are ammended as under, Ammended rates shall be applicable with effect from the date of issue i.e. 06/06/2018

Chapter- 5 Reinforced Cement Concrete ^l
Reinforced Cement Concrete _{c16}

Item No.	Existing		Ammendment			
	Description	Old		Description	New	
		Unit	Rate (Rs. in)		Unit	Rate (Rs. in)
5.34	Providing and fixing in position factory made precast RCC M-40 doors and windows frames having excellent smooth finish as per IS : 6523 with reinforcement of 3 Nos. 6mm dia main bars tied with 3 mm M.S. stirrups places @ 200 mm C/C and 6 numbers high strength polymer blocks of required size for fixing hinges including providing 6 no specially designed M.S. galvanised sleeves for accomodating 6 mm dia fully threaded bolts for fixing hold fast on vertical members, providing suitable arrangement for recieving sliding door bolts and tower bolt etc all complete, as per the direction of Engineer in charge. (The cost of hold fast and Cement Concrete block of 1:3:6 (1 Cement :3 sand : 6 Graded stone agreegate 20 mm nominal size) mix is also included in the item) The frame shall be measured in running meter correct to two places of decimal.			Providing and fixing in position factory made precast RCC M-40 door, window and ventilator frames having excellent smooth finish as per IS : 6523 with 6 mm dia main reinforcement of 3 nos. (for single rebate) and 4 nos. (for double rebate) tied with 3 mm mild steel stirrups @ 200 mm c/c, 6 numbers (for single rebate) and 12 numbers (for double rebate), with high density virgin polymer blocks of size 25X25X125 mm, each block having at least four holder blocks with holes for passing one of the main reinforcement bars for fixing hinges, providing vertical member with 6 numbers specially designed M.S. galvanised sleeves for accomodating 6 mm dia. fully threaded bolts for fixing hold fast and hole caps for recieving sliding door bolts (L-drop), proving virgin high density polymer blocks for fixing socket of tower bolt etc. complete, as per the direction of Engineer in Charge. The cost of hold fast and cement concrete block of 1:3:6 (1 Cement :3 Sand : 6 Graded stone agreegate 20 mm nominal size) mix included in the item.		
5.34.1	Door frame 125 mm x 60 mm	RM	316.00	5.34.1.1 Door frame 125 mm x 60 mm (double rebate)	RM	316.00
5.34.2	Door frame 100 mm x 60 mm	RM	289.00	5.34.2.1 Door frame 100 mm x 60 mm (single rebate)	RM	289.00

[Signature]
6/6/2018

5.34.3	Door frame 85 mm x 60 mm	RM	275.00	5.34.3 Window frame 125 mm x 60 mm (double rebate) with holes between rebates to hold fast grill or steel bar	RM	340.00
				5.34.4 Window frame 100X60 mm (Single rebate)	RM	300.00
				5.34.5 Ventilator frame 125 mm x 60 mm (double rebate) grooves for louvers at an angel of 45 degree at spacing to block direct vision	RM	340.00
				5.34.6 Ventilator frame 100 mm x 60 mm (single rebate) grooves for louvers at an angle of 45 degree at spacing to block direct vision and also holes 40 hold fast grill or steel bars.	RM	316.00

Project Director
P.W.D. RIU Bhopal


Bhopal, Dated 6/06/2018

Endt. No. F-64-10/2018/Common SOR/Building/W-1/PD/498

Copy is forwarded to:-

1. P.A to Hon'ble Minister, M.P. P.W.D. Bhopal
2. The Principal Secretary to Govt. of M.P. P.W.D. Bhopal
3. The Secretary to Govt. of M.P. P.W.D. Bhopal
4. The Engineer-in-Chief, M.P. P.W.D. Bhopal
5. The Chief Technical Examiner, M.P. Bhopal.
6. The Principal Secretary to Govt. Of M.P. Housing & Environment Bhopal.
7. The Accountant General, M.P. Gwalior/Bhopal.
8. The Secretary to Hon'ble Lokayukta, M.P. Bhopal.
9. The Chief Engineer, P.W.D. ----- M.P.
10. The Additional Project Director P.W.D. (PIU) ----- M.P.

11. The Chief Engineer, M.P. R.D.C. Bhopal.
12. The Chief Engineer, Rural Engineering Services, M.P. Bhopal
13. The Divisional Project Engineer M.P. PWD -----
14. The Executive Engineer, MP P.W.D. Division
15. Chairman, Contractor Association, MP Bhopal.


Project Director
PWD PIU Bhopal
6/6/2018
6/6