

**OFFICE OF THE PROJECT DIRECTOR  
MPPWD(PIU) NIRMAN BHAWAN, BHOPAL  
SCHEDULE OF RATES FOR BUILDING WORKS (w.e.f. 01.08.2014)**

**(Amendment No. 39)**

**The following items are amended as under in Building SOR w.e.f. 1/8/2014 and rate shall be applicable with effect from the date of issue of this order i.e. 05/06/2018**

**CHAPTER NO. 17  
Sanitary Installations**

| Item No.  | Existing   |       |        | Amendment   |  |              |
|-----------|--|-------|--------|---|--|--------------|
|           | Description  | Unit  | Rate   | Description                                       | Unit   | Rate         |
| 17.32     | Providing and fixing soil, waste and vent pipes :                              |       |        | Providing and fixing soil, waste and vent pipes : |  |              |
| 17.32.1   | 100 mm dia. Pipe minimum wall thickness 5mm                                    |       |        | 17.32.1   | <b>CI pipe (Sand cast) :-</b>  |              |
| 17.32.1.1 | Sand cast iron SandS pipe as per IS: 1729.                                     | meter | 791.00 | 17.32.1.1   | 100 mm dia Sand cast iron socket and spigot (S &S) pipe as per IS: 1729. wall thickness 5 mm   | meter 791.00 |
| 17.32.1.2 | Centrifugally cast (spun) iron socket and spigot (SandS) pipe as per IS: 3989. | meter | 860.00 |   | <b>Deleted</b>   |              |
|           |  |       |        | 17.32.1.3   | 75 mm dia Sand cast iron socket and spigot (S &S) pipe as per IS: 1729. wall thickness 5 mm  | meter 645.00 |
| 17.32.2   | 75 mm dia pipe minimum wall thickness 5mm                                      | meter | 791.00 | 17.32.2   | <b>CI (Spun cast) :-</b>   |              |
|           |  |       |        | 17.32.2.1   | 100 mm dia centrifugally cast (spun) iron socket and spigot (S &S) pipe as per IS: 3989. wall thickness 4 mm   | meter 860.00 |
| 17.32.2.2 | Centrifugally cast (spun) iron socket and pipe as per IS: 3989.                | meter | 860.00 |   | <b>Deleted</b>   |              |
|           |  |       |        | 17.32.2.3   | 75 mm dia centrifugally cast (spun) iron socket and spigot (S &S) pipe as per IS: 3989. wall thickness 4 mm  | meter 723.00 |
|           |  |       |        | 17.32.3   | <b>CI (Hubless) :-</b>   |              |
|           |  |       |        | 17.32.3.1   | 100 mm dia Hubless centrifugally cast (spun) iron pipes epoxy coated inside & outside including complete coupling assembly (EPDM rubber gasket stainless steel clamp and external metallic/protective shield as per IS: 15905) wall thickness 3.5 mm | meter 860.00 |
|           |  |       |        | 17.32.3.2   | 75 mm dia Hubless centrifugally cast (spun) iron pipes epoxy coated inside & outside including complete coupling assembly (EPDM rubber gasket stainless steel clamp and external metallic/protective shield as per IS: 15905) wall thickness 3.5 mm  | meter 723.00 |

page 1 of 2

4/16

Copy is forwarded to:-

1. P.A to Hon'ble Minister, M.P P.W.D. Bhopal
2. The Principal Secretary to Govt. of M.P.P.W.D. Bhopal
3. The Secretary to Govt. of M.P.P.W.D. Bhopal
4. The Engineer-in -Chief, M.P.P.W.D. Bhopal
5. The Chief Technical Examiner, M.P. Bhopal.
6. The Principal Secretary to Govt. Of M.P. Housing & Environment Bhopal.
7. The Accountant General, M.P. Gwalior/Bhopal.
8. The Secretary to Hon'ble Lokayukta, M.P. Bhopal.
9. The Chief Engineer, P.W.D ----- M.P.
10. The Additional Project Director P.W.D. (PIU) ----- M.P.
11. The Chief Engineer, M.P. R.D.C. Bhopal.
12. The Chief Engineer, Rural Engineering Services, M.P. Bhopal
13. The Divisional Project Engineer M.P. PWD -----
14. The Executive Engineer, MP P.W.D. Division
15. Chairman, Contractor Association, MP Bhopal.

Project Director  
PWD PIU Bhopal

5/6/2018

page 2 of 2 1/16