

**OFFICE OF THE PROJECT DIRECTOR  
MPPWD(PIU) NIRMAN BHAWAN, BHOPAL  
SEHEDULE OF RATES FOR BUILDING WORKS (w.e.f. 01.08.2014)**

**(AMMENDMENT No. 12)**

**The rate of following item ( Building SOR w.e.f. 1/8/2014) is ammended as under and rate shall be applicable with effect from the date of issue i.e.  
07 /11/2015**


**CHAPTER NO. 05**

**Reinforced Cement Concrete**

**SEHEDULE OF RATES FOR BUILDING WORKS (w.e.f. 01.08.2014)**

**Ammendment No 12 issue date 07.11.2015**

Item No.	Existing		Ammendment			
	Description	Unit	Rate	Description	Unit	Rate
5.27	Providing and laying in position machine batched, machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centring, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in charge. (Note:- Cement content considered in this item is 330 kg/cum/excess/less cement used as per design mix is payable/recoverabele separately)			Providing and laying in position machine batched, machine mixed cement concrete (BMC) of M-25 grade for reinforced cement concrete work using cement content as per approved mix design including use of admixtures in recommended proportions as per IS 9103 to accelerate/retard setting improve workability of concrete without impairing strength and durability as per direction of Engineer-in charge and pumping of concrete to site of laying and finishing but excluding the cost of centering, shuttering, and reinforcement. (Note:- minimum cement content is 330 kg/cum)		
	5.27.1 All works upto plinth level.	cum	5641.00	5.27.1 All works upto plinth level.	cum	5641.00
	5.27.2 All works above plinth level and upto floor five level.	cum	5757.00	5.27.2 All works above plinth level and upto floor five level.	cum	5757.00
				5.27.3 Add extra for each additional floor for all works above floor five level.	cum	30.00

  
7/11/2015  
Project Director  
MP PWD PIU BHOPAL

5.28	Extra for providing richer mixes at all floor levels. (Note :- If excess/less cement over the specified cement content used is payable/recoverable separately)				Extra for providing richer mixes of BMC as per item No 5.27 upto plinth level and at all floor levels.	
	5.28.1 Providing M-30 grade concrete instead of M-25 grade BMC/RMC	70.00	cum	70.00	5.28.1 Providing M-30 grade concrete instead of M-25 grade. (Note:- minimum cement content is 340 kg/cum)	70.00
	5.28.2 Providing M-35 grade concrete instead of M-25 grade BMC/RMC Note:- Cement content considered in M-35 is @ 350 kg/cum	140.00	cum	140.00	5.28.2 Providing M-35 grade concrete instead of M-25 grade (Note:- Minimum cement content is @ 350 kg/cum)	140.00
	5.28.3 Providing M-40 grade concrete instead of M-25 grade BMC/RMC (Note:- Cement content considered in M-40 is @ 360 kg/cum)	210.00	cum	210.00	5.28.3 Providing M-40 grade concrete instead of M-25 grade (Note:- Minimum cement content is @ 360 kg/cum)	210.00
5.29	Add/deduct for using extra/less cement in the items of design mix over and above the specified cement content therein.	669.00	Quin tal.		<b>DELETED</b>	

*[Handwritten Signature]*  
27/11/2015

Project Director  
MP PWD PIU BHOPAL

<p>5.31 Providing and laying in position ready mixed M-25 grade concrete for reinforced cement concrete work, using cement content as per approved design mix and manufactured in fully automatic batching plant and transported to site of work in transit mixer for all leads, having continuous agitated mixer, manufactured as per mix design of specified grade for reinforced cement concrete work, including pumping of R.M.C. for transit mixer to site of laying, excluding the cost of centering, shuttering, finishing and reinforcement, including cost of admixtures in recommended proportions as per IS:9103 to accelerate/retard setting, improve workability without impairing strength and durability as per direction of the Engineer-in-charge. (Note:- Cement content considered in this item is @ 330 kg/cum/Excess/less cement used as per design mix is payable/recoverable separately)</p>	<p>5.31.1 All works upto plinth level. 5.31.2 All works above plinth level and upto floor V level.</p>	<p>cum cum</p>	<p>6280.00 6434.00</p>	<p>Providing and laying in position ready mixed concrete (RMC) of M-25 grade for reinforced cement concrete work manufactured in fully automatic batching plant using cement content as per approved mix design and admixtures in recommended proportions as per IS:9103 to accelerate/retard setting, improve workability of concrete without impairing strength and durability as per direction of the Engineer-in-charge, and transported to site of work in transit mixer for all leads, continuous agitated, including pumping of R.M.C. from transit mixer to site of laying and finishing but excluding the cost of centering, shuttering, finishing and reinforcement. (Note:- minimum cement content in this item is @ 330 kg/cum)</p>	<p>cum cum</p>	<p>6280.00 6434.00 30.00</p>
---	--	--------------------	----------------------------	---	--------------------	--------------------------------------

The above amendment shall be applicable with effect from the date of issue i.e. 07.11.2015

*[Signature]*  
7/11/2015

Project Director  
PWD PIU Bhopal  
Subject Director  
PIU Bhopal



Endt. No. F-64-10 /2015/Common SOR/Building/W/PD/2015/ 4838

Bhopal, Dt. 07 /11/2015

**Copy is forwarded to:-**

1. P.A to Hon'ble Minister, M.P. P. W. D. Bhopal
2. The Principal Secretary to Govt. of M.P. P. W. D. Bhopal
3. The Secretary to Govt. of M.P. P. W. D. Bhopal
4. The Engineer-in -Chief, M.P. P. W. D. Bhopal
5. The Chief Technical Examiner, M.P. Bhopal.
6. The Principal Secretary to Govt. Of M.P. Housing & Environment Bhopal.
7. The Accountant General, M.P. Gwalior/Bhopal.
8. The Secretary to Hon'ble Lokayukta. M.P. Bhopal.
9. The Chief Engineer, P. W. D. ----- M.P.
10. The Additional Project Director P. W. D. (PIU) ----- M.P.
11. The Chief Engineer, M.P. R. D. C. Bhopal.
12. The Chief Engineer, Rural Engineering Services, M.P. Bhopal
13. The Commissioner, Housing Board, M.P. Bhopal.
14. The Commissioner, Bhopal.
15. The Collector, Bhopal.
16. The Superintending Engineer, Capital Project Circle CPA Bhopal.
17. The Superintending Engineer M.P. PWD -----
18. The Divisional Project Engineer M.P. PWD -----
19. The Executive Engineer, MP P. W. D. Division
20. Chairman, Contractor Association, MP Bhopal.

  
7/11/2015  
Project Director  
P.W.D. Bhopal